

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20857-00-00
Spot: NENWNE Sec/Twnshp/Rge: 30-20S-5W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: KNIGHT-TONN Well #: 1
County: MCPHERSON Total Vertical Depth: 3382 feet

Operator License No.: 6523
Op Name: SCHMIDT, KERMIT
Address: 308 WESTLANE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF		209		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/30/1996 3:30 PM
Plug Co. License No.: 4873 Plug Co. Name: D & R WELL SERVICE, INC.
Proposal Rcvd. from: KERMIT SCHMIDT Company: KERMIT SCHMIDT OIL OEPRATIO Phone: (316) 241-1255

Proposed
Plugging
Method:

SAND TO 3275' AND TOP WITH 5 SACKS OF CEMENT. RIP PIPE. PULL PIPE TO 750' AND SPOT 35 SACKS OF CEMENT. PULL PIPE TO 300' AND CIRCUALTE CEMENT TO THE SURFACE. 5 1/2" CASING AT 3381'.

Plugging Proposal Received By: PHIL WORLEY WitnessType: PARTIAL
Date/Time Plugging Completed: 10/31/1996 9:45 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SANDED TO 3290' AND TOPPED WITH 6 SACKS OF CEMENT. RIPPED PIPE AT 2200'. PULLED PIPE TO 765' AND SPOTTED 1 1/2 YDS SLURRY MIX. (3290 LBS OF CEMENT, 175 GALLONS H2O, AND 3 OZ A.E.A.) PULLED REMAINING PIPE. RAN 2" TUBING TO 300'. CIRCULATED 5 YDS OF SLURRY MIX (11,650 LBS OF CEMENT, 620 GAL H2O, AND 10 OZ A.E.A.) TO SURFACE. RECOVERED 2200' OF 5 1/2" CASING.

Perfs:

Top	Bot	Thru	Comments
3324	3330		

INVOICED
DATE 3-12-08
INV. NO. 2008061353

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 28 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 6 1/2 YDS OF SLURRY MIX BY MCPHERSON CONCRETE, INVOICE #182

Plugged through:

District: 02

Signed Michael Wilson
(TECHNICIAN)