

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-21139-00-00
Spot: NESWSW Sec/Twnshp/Rge: 30-20S-5W
4465 feet from N Section Line, 1233 feet from W Section Line
Lease Name: KNIGHT-TONN Well #: 2
County: MCPHERSON Total Vertical Depth: 3389 feet

Operator License No.: 6523
Op Name: SCHMIDT, KERMIT
Address: 308 WESTLANE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF		210		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/1996 9:30 AM
Plug Co. License No.: 4873 Plug Co. Name: D & R WELL SERVICE, INC.
Proposal Rcvd. from: KERMIT SCHMIDT Company: KERMIT SCHMIDT OIL OPERATIO Phone: (316) 241-1255

Proposed Plugging Method: SAND TO 3270' AND TOP WITH 5 SACKS OF CEMENT. RIP PIPE. PULL PIPE TO 750' AND SPOT 35 SACKS OF CEMENT. PULL PIPE TO 300' AND CIRCULATE CEMENT TO SURFACE. 5 1/2" CASING @ 3389'

Plugging Proposal Received By: PHIL WORLEY WitnessType: PARTIAL
Date/Time Plugging Completed: 11/01/1996 11:30 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SANDED TO 3210' AND TOPPED WITH 6 SACKS OF CEMENT. RIPPED PIPE AT 2010'. PULLED PIPE TO 804' AND SPOTTED 1 1/2 YDS SLURRY MIX (3495 LBS OF CEMENT, 180 GALLS H2O, AND 3 OZ. A.E.A. PULLED PIPE OUT OF HOLE. RAN 2" TUBING TO 300' AND CIRCULATED 5 YDS SLURRY MIX (11,650 LBS OF CEMENT, 650 GALLONS OF H2O, AND 10 OZ A.E.A.) RETRIEVED 2010' OF 5 1/2" CASING.

Perfs:

Top	Bot	Thru	Comments
3318	3358		

NVOICED
DATE 3-12-08
INV. NO 2008061353

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 28 2008

Remarks: USED 6 1/2 YDS OF SLURRY MIX BY MCPHERSON CONCRETE, INVOICE #3

CONSERVATION DIVISION
WICHITA, KS

Plugged through:

District: 02

Signed Michael D Wilson
(TECHNICIAN)

PWT