

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

051-20965-00-00

Lease Operator: Dreiling Oil, Inc.
Address: P.O. Box 550 Hays, Kansas 67601
Phone: (785) 625-8237 Operator License #: 5145
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4-24-08 (Date)
by: Bruce Basye (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3386 Bottom: 3399 T.D. 3399
L-KC Depth to Top: 3060 Bottom: 3304 T.D. _____
Toronto Depth to Top: 3032 Bottom: 3040 T.D. _____

API Number: 15 - (6-20-74)
Lease Name: Dreiling "F"
Well Number: 25
Spot Location (QQQQ): _____ - SE - SW - NW
2310 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 3 Twp. 12 S. R. 16 East West
County: Ellis
Date Well Completed: 6-20-74
Plugging Commenced: 6-25-08
Plugging Completed: 6-25-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Oil and water	3386	3392'	8 5/8"	200'	None
L-KC	oil and water	3074'	3221'	5 1/2"	3400'	None
Toronto	Oil and water	3032	3034			
Topeka	Oil and water	2988'	2991'			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran Tubing open ended to 2100'. Mixed 300 sxs. 60/40 Poz, 4% Gel with 300# Hulls. Pulled up to 1000' and mixed 55 sx. 60/40 Poz, 4% Gel and 200# Hulls. Cement Circulated. Tied to 5 1/2" Casing and mixed 18 sxs. 60/40 Poz, 4% Gel and pressured to 300#.
SIP- 300#. TIED TO 8 5/8" Casing and mixed 20 sxs. 60/40 Poz, 4% Gel and 50# Hulls. Holed loaded and stayed full. Job Complete.

Name of Plugging Contractor: Allied Cementing Company, LLC License #: 99996 KCC
Address: Russell, Kansas
Name of Party Responsible for Plugging Fees: DREILING OIL, INC.
State of Kansas County, Ellis, ss.

RECEIVED
KANSAS CORPORATION COMMISSION
APR 30 2008

Terry W. Plester (Employee of Operator) or (Operator) on above described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well, and the same are true and correct, so help me God.

(Signature) Terry W. Plester
(Address) P.O. Box 550, Hays, Kansas 67601

SUBSCRIBED and SWORN TO before me this 28th day of APRIL, 2008
Patricia Dreiling My Commission Expires _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202