

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Gamma Resources, Inc.  
Address: P.O. Box 800 Liberal, Kansas 67905  
Phone: (620) 624-6405 Operator License #: 34029  
Type of Well: D&A Coas KCCPKT Per CP 213 Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 4/16/2008 (Date)  
by: Lynn Reimer (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

API Number: 15 - 175-20106-00-01  
Lease Name: Black  
Well Number: # 1  
Spot Location (QQQQ): \_\_\_\_\_ - C - NW - NE  
660 Feet from  North /  South Section Line  
1980 Feet from  East /  West Section Line  
Sec. 11 Twp. 34 S. R. 31  East  West  
County: Seward  
Date Well Completed: \_\_\_\_\_  
Plugging Commenced: 3/18/2008  
Plugging Completed: 3/22/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	1507'	9 5/8"	1507'	None
		Surface	4466'	7"	4466'	1558'
		Surface	3175'	4 1/2"	3175'	2062'
		3068'	3623'	3 1/2" Flush Jt	555'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.  
Run tbg to 3068' & circ hole w/ mud & spot 20 sks cement up to 2818' . Cut & pull 4 1/2" csg from 2062' , Run tbg @ 2062' & spot 25 sks class "C" cement up to 1934' . Cut & pull 7" csg from 1558' . Run tbg @ 1557 & spot 50 sks cement up to 1325' , pull up hole w/ tbg to 600' & spot 40 sks cement . Top out 40' - 4' w/ 15 sks cement . Dig out & cut off 9 5/8" csg 4' below ground level & weld ID plate .

Name of Plugging Contractor: Orr Enterprises, Inc. License #: 33338  
Address: P. O. Box 1706 Duncan, OK 73534  
Name of Party Responsible for Plugging Fees: Gamma Resources, Inc  
State of Kansas County, Seward, ss.

*KCCPKT per open Ronda Maxwell*  
RECEIVED  
KANSAS CORPORATION COMMISSION

Ronda Maxwell (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well, and the same are true and correct, so help me God.

**JOY L. BEASLEY**  
Notary Public - State of Kansas  
My Appt. Expires 08-17-2010

(Signature) Ronda Maxwell  
(Address) P.O. Box 800, Liberal, KS 67905-0800

SUBSCRIBED and SWORN TO before me this 29 day of April, 2008  
Joy L. Beasley My Commission Expires: 08-17-2010  
Notary Public