

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: John J. Darrah, Jr.
Address: 225 N. Market #300, Wichita, KS 47202
Phone: (316) 219-3398 Operator License #: 5088
Type of Well: SWD EOR KCCPRT Per CP2/3 Docket #: E-21,504
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4/14/06 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Disposal Depth to Top: 3390 Bottom: 3406 T.D. 3600
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-20094-00-01
Lease Name: MORRIS OWWD KCCPRT
Well Number: 1 Per CP2/3
50'S + 50' WOF
Spot Location (QQQQ): NE - NE - SW
2360 Feet from North / South Section Line
3020 Feet from East / West Section Line
Sec. 31 Twp. 20 S. R. 13 East West
County: Pawnee
Date Well Completed: _____
Plugging Commenced: 4/16/08
Plugging Completed: 4/16/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	250	8 5/8	250	0
		0	3628	4 1/2	3628	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

2 3/8 TUBING TO 3100, Mixed and pumped 5 sks gel, and 50 sks 60-40 poz with 4% gel and 200 # hulls.
TUBING TO 1550, Mixed and pumped 50 sks cement as before with 100 # Hulls
TUBING TO 800, mixed and pumped 110 sks as before with 150# hulls which circulated to the surface, Topped off with 15 sks
Tried to pump into 8 5/8 X 4 1/2 annulus, blew ring off Bradenhead, standing full.

Name of Plugging Contractor: Copeland Steurs Well Service Inc License # 3004 32983
Address: Box 438, Haysville, KS KCCPRT Per CP2/3
Name of Party Responsible for Plugging Fees: Above
State of Kansas County, Sedgwick, ss.

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 05 2008

G. P. Staepelwerth, Agent (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) G. P. Staepelwerth, Agent
(Address) above

SUBSCRIBED and SWORN TO before me this 30th day of April, 2008
Susan Utterback My Commission Expires: 9/18/2010
Notary Public



