

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas**

A blank 4x4 grid of squares, intended for drawing a 3D object.

Name of Conservation Agent who supervised plugging of this well Mr. A. L. Laman
Producing formation Simpson Depth to top 2988 Bottom _____ Total Depth of Well 2995 Feet
Show depth and thickness of all water, oil and gas formations.

CASING RECORD

[illegible]

5 sacks cement on bottom, mud to 150' - 10' rock bridge &
15 sacks cement - mud to surface. 5 sacks cement for cap.

RECEIVED
STATE CORPORATIONS COMMISSION
2/14/51
FEB 14 1951
CONSERVATION DIVISION
Topeka, Kansas

Correspondence regarding this well should be addressed to W. G. Talbott
Address 708 Petroleum Bldg.

..... W. S. TALBOTT (employee of ~~owner~~ or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

rod.
W. B. Talbot


708 Petroleum Bldg.
(Address)

SUBSCRIBED AND SWORN to before me this 9 day of February, 1951.

Notary Public.

My commission expires.....October 13, 1952

22-5133-s 9-48-10M



COMPANY: Pabco and Sohio

FARM: Hawks #5
A 2000

NE NW NW

Sec. 26 Twp. 23 Rge. 3E

Total Depth: 2995

Comm: 5-25-47 Comp: 6-18-47

Elevation: 1329 Rot. Bush.
Production:Casing: 8 5/8" 154'
5 1/2" 2975'

2250-
Top K.C. 2300 by time log
2320 dark shale
2500 light chrystalline lime
-10 no sample
-20 light chrystalline lime
-30 dark shale
-40 dark shale and light lime
-70 light lime
-80 black shale
2600 light tan chrystalline lime
-10 black shale
-40 shale and shells
-50 light tan chrystalline lime
-80 gray shale
2700 shale and shells
-60 dark shale
-70 lime
Top Miss. 2771 by time log
-30 various colored shale and Miss. lime
-90 white chrystalline lime and chert
Base Miss. 2907 by time log
2920 white chrystalline lime
-75 black shale Rotary T.D.
-88 black shale
Top Simpson 2988
-90 cemented sand, light stain
-95 sand, stained, free oil

Total Depth 2995 from R.B.

PLUMBING
FILE SEC. 26 Twp. 23 Rge. 3E
54 100 20