

WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Butler County, Sec. 26 Twp. 28 Rge. 3 (E) (X)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines C SW NW

Lease Owner Talbott & Sohio

Lease Name Hawks Well No. 13

Office Address 709 Petroleum Building

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 8, 1948

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced December 23, 1948

Plugging completed December 27, 1948

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Loman

Producing formation Depth to top Bottom Total Depth of Well 2987 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Simpson sand, Water, 8 5/8", 175', none. Row 2: Simpson sand, Water, 5 1/2", 2960, 2947.95.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 4 sacks Calseal (36') on bottom

mud to 180' 10 sacks of cement on

8' Rock Bridge at 172'

Mud to surface 3 sacks of cement for cap.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. G. Talbott

Address 709 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. G. Talbott

SUBSCRIBED AND SWORN to before me this 5 day of January 11/6/49 1949

My commission expires October 13, 1952

Notary Public signature and stamp

PLUGGING FILE SEC 26 T 28 R 3 E BOOK PAGE 76 LINE 40

Company: Talbott & Sohio
Farm: Hawks #13

Section 26, T 28 S, R 3 E
Butler County, Kansas
Cen. SW NW
Rotary Tools
Elevation: 1315'
Total Depth: 2987'
D & A

Comm: December 8, 1948
Comp: December 27, 1948
Contractor: Penguin Petroleum, Inc.

Casing: 8 5/8" @ 175'
5 1/2" @ 2960'

- 0-137 Clay shells
- 145 Sand
- 175 Lime and shale
- 270 Lime
- 390 Lime and shale
- 535 Lime broken
- 715 Lime and shale
- 1165 Shale
- 1510 Shale and lime
- 1715 Lime broken
- 2100 Lime and shale
- 2137 Lime
- 2220 Shale
- 2298 Shale and shells
- 2745 Lime
- 2763 Shale
- 2880 Lime
- 2960 Lime and shale
- 2980 Dark shale
- 2987 Sand

R.U.S.T.

Total Depth @ 2987'


- Tops: Kansas City limestone @ 2298'
- Mississippian limestone @ 2761'
- Kinderhook @ 2901'
- Simpson sandstone @ 2980'

Small show of oil and 3 bailers of water @ 2984-87'

Certified to be a true copy of the well log as indicated on daily drilling reports.

Penguin Petroleum, Inc.

by



Subscribed and sworn to before me, the undersigned, a Notary Public in and for Sedgwick County, Kansas, this 29th day of December, 1948.

My Commission Expires: _____

October 13, 1952


Notary Public

RECORDED

JAN 6 - 1949

SECTION
COLLECTION
KANSAS

PLUGGING
FILE SEC 26-T-29R3E
BOOK PAGE 76 LINE 40