

15-015-19890-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Butler County. Sec. 27 Twp. 28S Rge. 3E (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE NE

Lease Owner W. G. Talbott, et al

Lease Name Hawks Well No. 14

Office Address 709 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed January 23 19 49

Application for plugging filed May 29, 19 53

Application for plugging approved June 15, 19 53

Plugging commenced June 14, 19 53


Plugging completed June 18 19 53

Reason for abandonment of well or producing formation

Ceased to produce commercially

If a producing well is abandoned, date of last production May 28, 19 53

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Lawrence Matthews

Producing formation Simpson Depth to top 2969' Bottom Total Depth of Well 2977' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	188'	None
				5-1/2"	2955'	2615.13'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 5 sacks cement on bottom 2977'
Mudded hole to 200' of surface
Set 15' rock bridge
Dumped 10 sacks cement
Mudded hole to 20' of surface
Set 5' rock bridge
Dumped 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chet Myerst

Address Masonic Building, Augusta, Kansas


STATE OF Kansas, COUNTY OF Butler, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Chet Myerst
Augusta, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 25 day of June, 1953

My commission expires Dec. 17, 1955



RECEIVED
STATE CORPORATION COMMISSION
6/30/53
JUN 30 1953
Notary Public.

PLUGGING
FILE SEC 27 T 28 R 3E
BOOK PAGE 108 LINE 5

Company: Talbott & Sohio
Farm: Hawks #14
Comm: January 10, 1949
Comp: January 23, 1949
Contractor: Penguin Petroleum, Inc.

Section 27, T 28 S, R 3 E
SW SE NE
Butler County, Kansas
Rotary Tools
Elevation: 1298' D.P.
Total Depth: 2977'
Initial Potential:

Casing: 8-5/8" @ 198'
5-1/2" @ 2955' - 2948' RTD

0-60	Clay
-70	Sand
-115	Clay
-130	Sand
-188	Shale & lime
-535	Lime & Shale
-720	Lime broken
-1170	Shale
-1495	Shale & Lime
-1695	Shale and shells
-2018	Shale and lime
-2375	Lime
-2378	Shale and shells
-2530	Lime
-2510	Shale and lime
-2750	Shale and shells
-2765	Shale and shells
-2360	Lime
-2955	Shale
-2963	Dark shale
-2977	Sand, Hammer show of oil Oil @ 73-74

Total Depth @ 2977'

Tops: Kansas City limestone	@ 2230'
Mississippian limestone	@ 2756'
Kinderhook	@ 2901'
Simpson sandstone	@ 2969'

Certified to be a true copy of the well log as indicated on daily drilling reports.

Penguin Petroleum, Inc.

by (Signed) JACK BROWN

Subscribed and sworn to before me, the undersigned, a Notary Public in and for Sedgwick County, Kansas, this 14th day of February, 1949.

My Commission Expires:

October 15, 1952

(Signed) B. D. STRICKLAND
Notary Public

PLUGGING
F&R SEC 27 28 26
BOOK PAGE 168 UNIT 3

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1953
CONSERVATION DIVISION
Wichita, Kansas