

*Q*


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Butler County. Sec 30 Twp. 28 Rge. 3 (E) XXX

Location as "NE/CNW/SW" or footage from lines NE NE SW  
Lease Owner T. L. Ferrier  
Lease Name Hoffman Well No. 1  
Office Address 300 Schweiter Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed January 3 19 59  
Application for plugging filed January 3 19 59  
Application for plugging approved January 3 19 59  
Plugging commenced January 3 19 59  
Plugging completed January 3 19 59  
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lee Guthrie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3292 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	293	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.


Hole filled with heavy rotary mud to 170 ft.  
Wood plug at 170 ft. with hulls & 15 sacks  
cement on plug. Hole filled with heavy  
rotary mud to 40 ft. Wood plug at 40 ft.  
with hulls and 10 sacks cement on plug. Rat  
hole filled with mud and capped with 2 sacks  
cement.

RECEIVED  
STATE CORPORATION COMMISSION  
12/5/61  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor White & Ellis Drilling, Inc.  
Address Box 448 El Dorado, Kansas

STATE OF Kansas COUNTY OF Butler, ss.  
Dale R. Daniel, employee of contractor \_\_\_\_\_ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale R. Daniel  
Box 448 El Dorado, Kansas  
(Address)



SUBSCRIBED AND SWORN TO before me this 5th day of January, 1959  
Ernest Siffard  
Notary Public.

15-015-00349-00-00

RP

Casing Record

Location: NE NE SW  
Sec. 30-28S-3E  
Butler County, Kans.  
Farm: Hoffman #1  
Well Owner: T.L. Ferrier  
Contractor: WHITE & ELLIS DRILLING, INC.  
Started: 12/26/58  
Completed: 1/3/59

8 5/8 293' cemented  
w/150 sacks

T.D. 3292'

Kelly bushing measurement 5' above ground level.

<u>FORMATION</u>	<u>DEPTH</u>
Soil	0-5
Lime	50
Shale	55
Lime	90
Shale	100
Red rock	105
Lime	120
Shale	160
Red rock	165
Lime	205
Shale	230
Red rock	240
Lime	275
Shale, black	285
Lime	529
Lime & shale stks.	910
Shale & shells	1060
Shale & lime	1080
Shale & lime stks.	1185
Lime & shale	1240
Shale & lime stks	1497
Lime	1535
Shale	1561
Lime & shale stks.	1630
Shale & shells	1708
Lime & shell stks.	1855
Lime	1864
Shale & lime stks.	1960
Sand	1986
Shale, sdy.	2020
Shale	2113
Lime, Lansing	2250
Shale	2454
Lime, Kansas City	2685
Shale	2746
Shale & lime	2795
Lime & shale	2940
Shale & lime	2999
Lime, Mississippi	3150
Shale	3222
Sand, Simpson	3278
Red rock	3280
Lime, Arbuckle N.S.O.	3292

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 5 1961  
CONSERVATION DIVISION  
Wichita, Kansas

Dry hole, plugged & abandoned