

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 015-23660 - 60-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 12/11/04

Well Operator: Hawkins Oil LLC KCC License #: 32693  
(Owner / Company Name) (Operator's)

Address: 427 S. Boston Ave. Suite #915 City: Tulsa

State: OK Zip Code: 74103 Contact Phone: ( 918 ) 382 - 7743

Lease: Girod B Well #: 5 Sec. 25 Twp. 25S S. R. 4  East  West

SW/4 - SE/4 - SE/4 Spot Location / QQQQ County: Butler

330 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

840 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8.625 Set at: 208' Cemented with: 85 Sacks

Production Casing Size: 5.5 Set at: 776' Cemented with: 60 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs from 704' to 734'

Elevation: 1413 ( G.L. /  K.B.) T.D.: 782 PBTD: 769 Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand fill 50' from PBTD. Dump bailer 5 sx cement on top.

MIT to ensure perfs are shut off. Shoot holes @ 260', circulate cement to surface, shut down.

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 14 2008

CONSERVATION DIVISION  
WICHITA, KS

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Ralph Baker

Phone: ( 316 ) 322 - 3506 MOBILE

Address: \_\_\_\_\_ City / State: \_\_\_\_\_

Plugging Contractor: Braden Petroleum & Plugging KCC License #: 32475  
(Company Name) (Contractor's)

Address: Post Office Box 282, Burden, KS 67019 Phone: ( 620 ) 222 - 1252

Proposed Date and Hour of Plugging (if known?): N/A

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4/9/08 Authorized Operator / Agent: [Signature]  
(Signature)

Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

# KANSAS

## CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HAWKINS OIL, LLC  
427 S BOSTON AVE STE 915  
TULSA, OK 74103-4114

May 01, 2008

Re: GIROD B #5  
API 15-015-23660-00-00  
25-25S-4E, 330 FSL 840 FEL  
BUTLER COUNTY, KANSAS


Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after October 28, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,



Steve Bond  
Production Department Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000