

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 151-22290-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 3-07-2008.

Well Operator: Shelby Resources, LLC and Captiva Energy, LLC KCC License #: 31725
(Owner / Company Name) (Operator's)

Address: P.O. Box 1213 City: Hays

State: Kansas Zip Code: 67601 Contact Phone: (785) 623 - 3290

Lease: Shrack Farms Unit Well #: 1 Sec. 15 Twp. 26 S. R. 13 East West

app. - SE - SE - SW Spot Location / QQQQ County: Pratt

596' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2355' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: 20" Set at: 80' Cemented with: 10 yds. of 8 sx. grout Sacks

Surface Casing Size: 8-5/8" Set at: 854.34' KB Cemented with: 500 Sacks

Production Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: _____

Elevation: 1935 (G.L. / K.B.) T.D.: 4638' PBTD: 4638' Anhydrite Depth: 832-845'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Heavy mud in the hole. Plug @ 4456', 880', 450', and 60'. Plug each with 40-50 sxs. Plug rathole and mousehole. Use 60/40 poz with 4% gel.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Both logs and ACO-1 will be filled in the next 30-45 days.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Brian Karlin
of Captiva Energy, LLC Phone: (785) 623 - 3290

Address: P.O. Box 1213 City / State: Hays, Kansas 67601

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99996
(Company Name) (Contractor's)

Address: P.O. Box 31, Russell, Kansas 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): 3-18-2008

RECEIVED
KANSAS CORPORATION COMMISSION

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3-28-2008 Authorized Operator / Agent: Brian Karlin
(Signature)

APR 04 2008

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA, KS

* Well plugged - kcc-dlg

Handwritten initials/signature