

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 185-23,067-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 09/17/1988

Well Operator: F.G. HOLL COMPANY L.L.C. KCC License #: 5056

Address: 9431 E. Central Suite #100 City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481

Lease: FAIR "A" Well #: 1-10 Sec. 10 Twp. 21S S. R. 11 East West

C - NE - NW - SW Spot Location / QQQQ County: STAFFORD

440' 2549 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1980' 4477 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: NONE Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 228'KB Cemented with: 240 Sacks

Production Casing Size: 4 1/2" Set at: 2556' KB Cemented with: 50 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2286'-2288', 2362'-2364', 2376-2378', BP@2527

Elevation: 1980' (G.L. / K.B.) T.D.: 2660" PBDT: 2527' Anhydrite Depth: 498'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): HEAVY MUD, HULLS, CEMENT AND PLUG ACCORDING TO KCC.

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

FEB 29 2008

If not explain why? _____

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: ROB LONG

Phone: (620) 793 - 0915


Address: P.O. BOX 158 City / State: BELPRE/KANSAS

Plugging Contractor: QUALITY WELL SERVICE KCC License #: 31925

Address: 190 US HIGHWAY 56 ELLINWOOD/KANSAS Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2/28/2008 Authorized Operator / Agent: ADAM T. THORNE 
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Fair 'A' 1-10

LOCATION: 100' South of C N/2 Nw Ne Section 10 T 21s R 11w
API: 15-185-230670000 Stafford County, Kansas

OWNER: F.G. Holl Company, L.L.C.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 21-Nov-97
COMPLETED: 26-Nov-97

TOTAL DEPTH: **DRILLER** 2660 FEET
LOGGER 2658 FEET

Ground Elevation: 1780
KB Elevation: 1789

LOG

0 - 200 FEET Top Soil and Sand
200 - 512 FEET Shale
512 - 530 FEET Anhydrite
530 - 2660 FEET Limestone, Shale and Dolomite

CASING RECORDS

Spud @ 10:30 am on 11-21-97. Drilled 12-1/4" hole to 230'. Ran 5 joints of new 20# 8-5/8" surface casing 216.16' set at 228' KB. Cemented with 240 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 2:00 pm on 11-21-97 by HOWCO. Good returns. Ticket # 308185.

Ran 64 jts used 4-1/2" casing. Tallied 2547.03', set at 2556.03' KB. Cemented with 25 sacks lite and 25 sacks FG Holl mix. Plug down at 7:15 am on 11-16-97 by HOWCO. Ticket # 308206. Centralizers on jts 1-3-8-10. Scratchers from 2260'-2310' and 2350'-2400'. Plug rathole with 15 sacks and plug mousehole with 10 sacks.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 29 2008

CONSERVATION DIVISION
WICHITA, KS

DEVIATION SURVEYS

1/4 degree(s) at 230 feet
1-1/4 degree(s) at 1630 feet



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

March 05, 2008

Re: FAIR A #1-10
API 15-185-23067-00-00
10-21S-11W, 2549 FSL 4477 FEL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after September 1, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888