

State of Kansas



15-065-02681-00-00

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 16 1963  
12-10-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Duane Born of Chem-Tech Services, Inc., has this date requested permission to plug the following described well:  
Morrison Producing Co.  
Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Morrison Producing Company,  
Complete Address: 400 N. Main, Box #712, Eldorado, Kansas.  
Lease Name: Law Well No. 2  
Location: SW-NW-SE Sec. 24 Twp. 8 Rge. (E) (W) 23  
County Graham Total Depth 3640' Oil Well  
Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Born was instructed to plug the well as follows:

268'--7" Surface pipe, cement circulated with 150 Sx.  
Circulate hole with heavy mud, set plug @ 550' & 15 Sx. cement.  
" " 250' & 15 Sx. cement.  
" " 40' with 1/2 Sk. hulls & 8 Sx. cement.

Very truly yours,

*N. L. Nichols*