



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 1 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

2/1/71

Dear Sir:

Mr. Deane Sharpe of Barnett Oil Company has this date requested permission to plug the following described well:

Mr. Sharpe guarantees payment of the plugging fee.

Operator's full Name: Barnett Oil Company,

Complete Address: 411 First National Bank Building, Wichita, Kansas.

Lease Name: Lyons Well No. 1

Location: SE-SE-SE Sec. 2 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3798' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sharpe was instructed to plug the well as follows:

110'--8 5/8" Surface casing, cement circulated with 100 Sx.
3797'--5 1/2" Production casing cemented on bottom with 100 Sx. Well
plugged back to 3788'. Top perforations @ 3620'.

Push plug to 3600', sand well back from 3600' to 3575' and set 5 Sx.
cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks
hulls, 30 sacks gel and 150 Sx. cement, staged.

Very truly yours,

A. G. Nichols
Conservation Division Agent