

State of Kansas



15-065 20099-00-00

State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
NOV 6 1967  
CONSERVATION DIVISION  
Wichita, Kansas  
11/6/67

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company has this  
date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation,

Complete Address: 412 Union Center, Wichita, Kansas.

Lease Name: Welty Well No. 2

Location: NW-NW-SW Sec. 2 Twp. 8 Rge. (E)(W) 24

County Graham Total Depth 371.1' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

109'--8 5/8" Surface pipe, cement circulated with 75 Sx.  
Dakota section from 810' to 1000'.

Circulate hole with heavy mud. Pull DP to 1025' and displace 100 Sx  
cement thru DP. Pull DP to 120' and displace 35 Sx. cement thru DP.

Very truly yours,

Conservation Division Agent