



15-0605-0274600-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 11 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pulley of Forbes Csg. Pulling Co., has this

date requested permission to plug the following described well:

John O. Farmer
Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 W. Wichita, Russell, Kansas.

Lease Name: Goff Well No. 4

Location: SE-NE-SW Sec. 8 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3770 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

155'--8 5/8" Surface pipe, cement circulated with 100 Sx.
3770'--5 1/2" Production casing cemented with 75 Sx. Top per-
forations from 3554' to 3558'.

Sand well to 3540' and set 5 Sx. cement with dump bailer.

Pull 5 1/2" casing and squeeze well with 35 sacks gel followed

by 100 Sx. cement.

Very truly yours,

H. L. Nichols
Conservation Division Agent