

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
NOV 16 1966
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dale Bucheister of John O. Farmer has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name: Kobler Well No. E-1

Location: NW-SE-NE Sec. 26 Twp. 8 Rge. (E)(W) 24

County Graham Total Depth 3830 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

174'--8 5/8" Surface pipe, cement circulated with 125 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	180'	with $\frac{1}{4}$ sk. hulls & 20 Sx. cement.
"	"	40'	with $\frac{1}{2}$ sk. hulls & 10 Sx. cement.

Very truly yours,

A. B. Doherty
Conservation Division Agent