

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21033-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 8-22S-14W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: ESTES Well #: 1  
County: STAFFORD Total Vertical Depth: 3875 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3615		WITH 1 SX CMT
PROD	5.5	3866	0	WITH 250 SX CMT
SURF	8.625	291		WITH 325 SX CMT

125.94

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/27/2008 8:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: KEVIN WILES Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: SAND TO 3816' WITH 5 SX CMT OR CIBP WITH 3 SX CMT. PLUG AT 880' WITH 15 SX GEL & 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/27/2008 3:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

COULDN'T GET PLUG PAST 3659'. SET CIBP @ 3615' & 1 SX CMT. PERFORATED 5 1/2" @ 880'. RAN TBG TO 899'. PUMPED 110 SX CMT DOWN TBG & HAD CMT TO SURFACE UP 5 1/2". CLOSED IN 5 1/2". PUMPED 165 SX CMT. LOST CIRCULATION ON 8 5/8" X 5 1/2". PULLED TBG. WAITED 4 HOURS. CMT TOP ON 5 1/2" =600'. PUMPED 110 SX CMT DOWN 5 1/2". PRESSURED & SHUT IN AT 1000 PSIG. PUMPED 50 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. SHUT IN AT 500 PSIG.

Perfs:

Top	Bot	Thru	Comments
3866	3872	OH	

**INVOICED**  
DATE 3-25-08  
INV. NO. 2008061400

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 17 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)