

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-21017-00-01  
Spot: SENENE Sec/Twnshp/Rge: 10-16S-26W  
033 feet from S Section Line, 1153 feet from E Section Line  
Lease Name: LEVI OWWO Well #: 3  
County: NESS Total Vertical Depth: 4635 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4635	0	WITH 200 SX CMT
SURF	8.625	281		WITH 200 SX CMT

150.64

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/05/2008 9:30 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: MARK LEIKER Company: BEREN CORPORATION Phone: (785) 628-6101

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP 35 SX CMT & 150# HULLS. PLUG AT 1500' WITH 40 SX CMT. TEST CASING TO 500#. IF HOLDS, PERFORATE AT 1200' & PUMP 80 SX CMT OVER CASING VOLUME. IF NO CIRCULATION OUT BACKSIDE PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/05/2008 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

**\*\*SQUEEZED WELL @ 2792' -2823' W/150 SX CMT, 2629-44' W/150 SX CMT, 2272-2304 W/250 SX CMT, 1800-43' W/143 GAL OF PERMASEAL, 1627-1808' W/160 SX CMT.\*\***  
RUN TBG TO 4100' & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 1500' & PUMP 50 SX COMMON CMT W/3% CC. WAIT 2 HOURS. PRESSURED CASING TO 500# & IT HELD. PERFORATED AT 1200'. TIED ONTO CASING AND PUMPED 135 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 350#. TIED ONTO BACKSIDE AND PUMPED 75 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4555	4558		
4551	4553		
4542	4546		
4534	4539		
2626	2644		
1627	1808		

**INVOICED**  
DATE 3-25-08  
INV. NO. 2008061402

RECEIVED  
KANSAS CORPORATION COMMISSION


**MAR 17 2008**

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed Michael Maier  
(TECHNICIAN)

Form CP 231  
*[Handwritten initials]*