

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22977-00-00
Spot: SENEW Sec/Twnshp/Rge: 11-25S-11W
990 feet from N Section Line, 2310 feet from W Section Line
Lease Name: GORDNER Well #: 1-11
County: STAFFORD Total Vertical Depth: 3960 feet

Operator License No.: 3180
Op Name: DEUTSCH, KENT A. DBA DEUTSCH OIL
Address: 8100 E 22ND ST N
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3951	2385	WITH 175 SX CMT
SURF	8.625	252		WITH 175 SX CMT

128.70

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/11/2008 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE'S TESTING & SALVA Company: MIKEL KELSO Phone: (620) 938-2943

Proposed Plugging Method: 5 SX CMT OF BOTTOM, 10 GEL & 50 SX CMT. @ 630 FT., 50 SX CMT@270 FT., 20 SX CMT@ 40 FT.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 03/11/2008 3:10 PM

Witness Type: COMPLETE (100%)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3400' & 4 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 630' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 270' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3799	3831		
3760	3764		
3447	3450		


INVOICED
DATE 3-25-08
INV. NO. 2008061404

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 17 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

Form CP-23