TO:

STATE CORPORATION COMMISSION **CONSERVATION DIVISION - PLUGGING**

130 SOUTH MARKET, SUITE 2078

WICHITA, KANSAS 67202

API Well Number: 15-185-23071-00-00

Spot: SWSWSW

Sec/Twnshp/Rge: <u>11-25S-11W</u>

330 feet from S Section Line,

330 feet from W Section Line

Lease Name: GORDNER

Well #: 2-11

County: STAFFORD

String Size

Total Vertical Depth: 4001 feet

Operator License No.: 3180

Op Name: DEUTSCH, KENT A. DBA DEUTSCH OIL

Address: 8100 E 22ND ST N WICHITA, KS 67226 PROD 5.5 3993 SURF 8.625 257

Depth (ft) Pulled (ft) Comments WITH 310 SX CMT

WITH 185 SX CMT

30.03

Well Type: OIL

UIC Docket No:

1800

Date/Time to Plug: 03/10/2008 9:00 AM

Plug Co. License No.: 31529

Proposal Rcvd. from: MIKE KELSO

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed 5 SX CMT OF BOTTOM, 10 GEL & 50 SX CMT @ 600 FT., 50 SX CMT @290 FT., 20 SX @ 40 FT.

Plugging Method:

Plugging Proposal Received By:

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/10/2008 11:10 AM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PLUGS WERE PUT 100' DEEPER THAN EXPECTED DUE TO PIPE COUNT BEING OFF 100'. SANDED TO 2775' & 5 SX CMT. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 700' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 380' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

_	•
ᅜᅀ	rte:
ГС	HJ.

Тор	Bot	Thru	Comments
3876	3884		
3859	3865		
3599	3602		
3539	3549		
3496	3502		
2828	2832		

RECEIVED KANSAS CORPORATION COMMISSION

Remarks:


Plugged through: CSG

USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

MAR 17 2008

CONSERVATION DIVISION WICHITA, KS

District: 01



(PÉCHNICIAN)

