

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22331-00-00
Spot: SWSESE Sec/Twnshp/Rge: 18-15S-22W
330 feet from S Section Line, 830 feet from E Section Line
Lease Name: SARGENT Well #: 1-18
County: TREGO Total Vertical Depth: 4380 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1685		
PROD	5.5	4375	0	150 SX CMT.
SURF	8.625	208	0	160 SX CMT.
T1	2.875	4326		

142.35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2008 3:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: RONALD SINCLAIR Company: GRAND MESA OPERATING COMPA Phone: (316) 265-3000

Proposed Plugging Method: Ordered 235 sxs SMD - 17 sxs gel - 500# hulls.
DV at 1685' w/155 sxs SMD.
Dakota 485'-785'. Anhy 1663'-1703'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2008 4:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Swift Services rigged to 5 1/2" casing with a swedge - pumped 50 sxs SMD with 300# hulls mixed in.
Pumped 17 sxs gel, followed with 175 sxs SMD with 200# hulls mixed in to pressure with Max. P.S.I. 500#. S.I.P. 500#.
Rigged to 8 5/8" - pumped 10 sxs SMD.
Max. P.S.I. 400#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
4224	4230		

INVOICED

DATE 3-25-08
INV. NO. 2008001408

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 17 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES, INC.-TICKET #13983.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

GRAND MESA OPERATING CO
WICHITA KS 67202

#1-18 SARGENT

18-15S-22W
160' E, C SW SE SE

site 7 N & 3-1/2 W OF BROWNELL KS

cy: TREGO

API 15-195-22331

contr: AMERICAN EAGLE DRLG #1

field: WOODSUN EXT (1/4 W)

geol: PATRICK J DEENIHAN


date 02/22/2006

spc date 03/10/2006

drig comp 03/19/2006

card issued 05/15/2006

last revised 05/15/2006



ELV: 2290 KB, 2283 GL
tops depth/datum
FBTD 4333 -2043
RTD 4380 -2090
NO TOPS RPTD

Awh Top +627
Base +587

IP status:

OIL, CHER, INTV NA, 04/19/2006
CSG: 8-5/8" 208 / 160 SX (ALT 2), PROD CSG NA, MULTI
STAGE COLLAR AT 1685 / 155 SX
COMMENT: PROPOSED START 3/1/2006
NO CORES OR DSTS RPTD
TRGT ZN: CHER SD (OIL), PTD 4360 (MISS), MICT - CO, PB
4333, PF (CHER SD) INTV NA, SWB DWN, GSO, POP, OIL
WELL (POTENTIAL NOT RPTD), 4/19/2006 - TIGHT HOLE -
NO OTHER INFO AVAILABLE - TEMP COMP 5/15/2006

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS