

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-21288-00-00

Spot: NWSESENE

Sec/Twnshp/Rge: 10-34S-25W

2240 feet from N Section Line,

400 feet from E Section Line

Lease Name: GOODNIGHT

Well #: 1

County: CLARK

Total Vertical Depth: 5920 feet

Operator License No.: 33384

Op Name: HIGH BLUFF OPERATING LLC

Address: 730 17TH ST STE 700  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5450		WITH 2 SX CMT
COND 20		120		50
PROD 4.5		5895	3260	WITH 360 SX CMT
SURF 8.625		719		WITH 400 SX CMT

192.40

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 03/10/2008 9:30 AM

Plug Co. License No.: 5112

Plug Co. Name: MIDWESTERN WELL SERVICE, INC.

Proposal Rcvd. from: MR. K.O. (SHINE) OVERBY Company: HIGH BLUFF OPERATING

Phone: (303) 295-2223

Proposed Plugging Method: CIBP @ 5450' & 2 SX CMT. PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 03/10/2008 11:15 AM

KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 5450' WITH 2 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1170' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 829' WITH 50 SX CMT. 3RD PLUG AT 519' WITH 43 SX CMT. 4TH PLUG AT 30' WITH 10 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5604	5610		
5592	5600		
5500	5505		

**INVOICED**  
DATE 3-25-08  
INV. NO. 2008061410

RECEIVED  
KANSAS CORPORATION COMMISSION


MAR 17 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

*Jerry W. Stapleton*  
(TECHNICIAN)  
PRT J

Form CP-2/3