

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21889-00-00
Spot: SENENW Sec/Twnshp/Rge: 36-29S-8W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SCHWARTZ Well #: 1
County: KINGMAN Total Vertical Depth: 4176 feet

Operator License No.: 32302
Op Name: KEY GAS CORP.
Address: 505 S BROADWAY STE 200
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF | 8.625 | 300 | | |

135.72

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/19/2004 4:30 PM
Plug Co. License No.: 33436 Plug Co. Name: FORREST ENERGY LIMITED LIABILITY CO
Proposal Rcvd. from: ROD ANDERSON Company: KEY GAS CORP Phone: _____

Proposed Plugging Method: 35 SKS 1150, 35 SKS 700', 35 SKS 350', 25 SKS 60', 15 SKS RAT HOLE, 10 SKS MOUSE HOLE

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 07/19/2004 8:15 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE DRILL PIPE WAS RUN IN OPEN END TO 1150', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 700', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 350', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 60', WHERE CMT WAS CIRC TO SURFACE. THE RAT HOLE WAS CIRC WITH 15 SKS OF CMT. THE MOUSE HOLE WAS CIRC WITH 10 SKS OF CMT.

Perfs:

INVOICED
DATE 3-29-08
INV. NO. 2008061413

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 17 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID AND CMT. 24744 40/60 POZ 4% GEL

Plugged through: DP

District: 02

Signed [Signature]
(TECHNICIAN)

[Handwritten initials]