

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23501-00-00
Spot: SENWSW Sec/Twnshp/Rge: 31-16S-24W
1749 feet from S Section Line, 3674 feet from E Section Line
Lease Name: MATTHEWS B Well #: 2
County: NESS Total Vertical Depth: 4505 feet

Operator License No.: 5215
Op Name: PHILLIPS, LEE E. DBA LEE PHILLIPS OI
Address: 151 WHITTIER STE 1400
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4501	0	WITH 200 SX CMT
SURF	8.625	323		WITH 225 SX CMT

146.41

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2008 9:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE Phone: (785) 731-5312

Proposed Plugging Method: RUN TBG TO 4400' & SPOT 35 SX CMT & 200# HULLS. PULL TBG TO 1700' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF WITH CMT. TIE ONTO BACKSIDE AND PUMP 50 SX CMT IF IT WILL TAKE IT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2008 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

5 1/2" CASING HAD BEEN CEMENTED TO SURFACE FROM 1100' WITH 200 SX CMT IN 1990. RUN TBG TO 4486' PUMP 20 SX GEL - 35 SX CMT - 200# HULLS. PULL TBG TO 1700' & PUMP 170 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4501	4505	OH	

INVOICED
DATE 3-25-08
INV. NO. 2008061414


RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

MAR 17 2008
CONSERVATION DIVISION
WICHITA, KS

District: 01



Signed

Michael Maier
(TECHNICIAN)