

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21524-00-00
Spot: NWSENE SW Sec/Twnshp/Rge: 27-19S-10W
1845 feet from S Section Line, 2145 feet from W Section Line
Lease Name: RINGWALD Well #: 7
County: RICE Total Vertical Depth: 3350 feet

Operator License No.: 33315
Op Name: MAR-LOU OIL CO., LLC
Address: PO BOX 218
WILSON, KS 67490

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3349	2200	150 SX CMT
SURF	8.625	216		185 SX CMT

108.88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2008 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/10/2008 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 3010 AND CAP WITH 5 SX'S CEMENT. CUT OFF CASING @ 2200' AND PULL TO 1200' AND PUMP 35 SX'S CEMENT, PULL CASING TO 850' AND PUMP 35 SX'S CEMENT, PULL CASING TO 266' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT OF HOLE AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3307	3310		
3298	3299		
3196	3200		
3158	3162		
3065	3069		

INVOICED
DATE 3-25-08
INV. NO. 2008061415

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 17 2008

Remarks: 60-40 POZ 4% GEL. QUALITY WELL TICKET #1870 - USED 145 SX'S TOTAL

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Virgil Clothier
(TECHNICIAN)