

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-081-21287-00-02
 Spot: NESWE Sec/Twnshp/Rge: 13-27S-34W
1259 feet from S Section Line, 1847 feet from E Section Line
 Lease Name: FREY MORROW UNIT Well #: 103 W
 County: HASKELL Total Vertical Depth: 5355 feet

Operator License No.: 5447
 Op Name: OXY USA INC.
 Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5110		
PC		3122		WITH 60 SX CMT
PKR		5028		
PROD 5.5		5355	2171	WITH 195 SX CMT
SURF 8.625		1783		WITH 425 SX CMT

174.04

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 02/28/2008 9:00 AM
 Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
 Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 100# HULLS & 25 SX CMT AT 5028'. PUMP 300# HULLS & 25 SX CMT AT 3800'. PLUG AT 1810' WITH 50 SX CMT. PLUG AT 830' WITH 830' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 02/29/2008 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 100# HULLS AT 5078-88' THROUGH TBG & MODEL D PACKER.
 PUMP 25 SX CMT & 400# HULLS AT 4076' THROUGH TBG. 1ST PLUG AT 1810' WITH 50 SX CMT. 2ND PLUG AT 830' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5120	5128		
5078	5088		
4260	4278		
4222	4240		
4108	4136		
4076	4082		

INVOICED

DATE 3-25-08

INV. NO. 2008061418

RECEIVED
 KANSAS CORPORATION COMMISSION


MAR 17 2008

CONSERVATION DIVISION
 WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01



Signed _____

Ken Jehlik

(TECHNICIAN)