

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20961-00-00
Spot: SWNENWNW Sec/Twnshp/Rge: 12-33S-6W
4680 feet from S Section Line, 4480 feet from E Section Line
Lease Name: WETHINGTON Well #: 1
County: HARPER Total Vertical Depth: 4808 feet

Operator License No.: 31925
Op Name: QUALITY WELL SERVICE, INC.
Address: 190 US HWY 56
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4808	3420	200 SX
SURF	8.625	307		200 SX <u>156.26</u>

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/19/2008 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND 50' ABOVE PERFS AND CAP WITH 4 SKS OF CMT, REC. CASING. 35 SKS 1150, 35 SKS 650, CIRC 350'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 02/19/2008 1:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE BOTTOM WAS PLUGGED BY PUMPING 100# HULLS AND 30 SKS OF CMT. TOC 3615'. THE CASING WAS RECOVERED FROM 3420' AND PULLED TO 1150', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED 50 650', WHERE 35 SKS FO CMT WAS SPOTTED. THE CASING WAS PULLED TO 350', WHERE CMT WAS CIRC TO SURFACE. THE REMAINING CASING WAS PULLED AND THE CMT WAS TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
4376	4380		
4358	4367		
3756	3760		
3748	3752		

INVOICED
DATE 3-25-08
INV. NO. 2008061421

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 17 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING 40/60 POZ 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)