

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21856-00-01
Spot: W2SWSE Sec/Twnshp/Rge: 36-30S-7W
667 feet from S Section Line, 2259 feet from E Section Line
Lease Name: HUFFORD Well #: 1
County: KINGMAN Total Vertical Depth: 4659 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4591	3600	135 SX
SURF	8.625	228		

151.42

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/28/2008 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed
Plugging
Method:

SAND TO 4290' CAP WITH 5 SKS CMT. REC CASING. 35.SKS 1300', 35 SKS 800', CIRC CMT FROM 280'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/29/2008 11:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE SANDED BACK TO 4220' AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM AND PULLED TO 1300', WHERE 35 SKS OF CMT WAS SPOTTED, THE CASING WAS PULLED TO 800', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 280', WHERE CMT WAS CIRCULATED TO SURFACE. THE REMAINING CASING WAS PULLED AND THE CMT WAS TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
4340	4346		SPF - NEW

INVOICED
DATE 3-25-08
INV. NO. 200806142


RECEIVED
KANSAS CORPORATION COMMISSION
MAR 17 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING 40/60 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

PKT