

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21706-00-00
Spot: SWSENW Sec/Twnshp/Rge: 15-19S-29W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: CLARK Well #: 1-15
County: LANE Total Vertical Depth: 4622 feet

Operator License No.: 5420
Op Name: WHITE & ELLIS DRILLING, INC.
Address: PO BOX 48848
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		2117		WITH 175 SX CMT
PROD	4.5	4622	0	WITH 75 SX CMT 150.22
SURF	8.625	268		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/06/2008 10:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: PUMP 200# HULLS & 40 SX CMT ABOVE PERFS. GEL SPACER TO 2100'. FILL CMT FROM 2100' TO SURFACE. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/06/2008 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4260' & SPOT 40 SX CMT & 200# HULLS. SPOT 12 SX GEL. PULLED TBG TO 2100' & PUMPED 135 SX CMT. CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4268	4270		

INVOICED
DATE 3-25-08
INV. NO. 2008061427

RECEIVED
KANSAS CORPORATION COMMISSION


MAR 17 2008

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 01



Signed

Michael Maier

(TECHNICIAN)

Form CP-213

PKT