

2 060443

11R

API NUMBER 15- 173-20682-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE SW, SEC. 5, T 26 S, R 2 W/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6190

Lease Name Voght "B" Well # 2

Operator: William G. Ash Gas & Oil
Name &
Address 500 North Sagebush
Wichita, KS 67230
316-733-5280

County Sedgwick 114.56
Well Total Depth 3,525 feet
Conductor Pipe: Size 5 1/2 feet 3,502
Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated P.B.T.D. 2995

Plugging Contractor B & S Well Service License Number 6013

Address Box 837, Winfield, KS 67156

Company to plug at: Hour: _____ Day: 3 Month: 11 Year: 19 86

Plugging proposal received from Dale Smith

(company name) B & S Well Service (phone) _____

were: Sand bottom 2,940 feet, dump six sacks cement. Shoot and pull pipe. Bail top down, build bridge at 300 feet to 275 feet and bail dry and dump five yards of sand redi mix.

Plugging Proposal Received by District Office - Ron Wilson (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:00 p.m. Day: 3 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT Sanded bottom to approximately 2,940 feet and dumped six sacks of portland cement. Shot and pulled approximately 2,300 feet of 5 1/2" casing. Could not bail, high heavy mud. United Cementing hooked to swedge in surface pipe and pumped three sacks hulls, ten sacks gel and 100 sacks of 60/40 POZ mix, 2% cc. P.I.P. - 500# psi S.I.P. - 300# p.s.i.

Remarks: United ticket #1959 (If additional description is necessary, use BACK of this form.)

NOV 10 11-10-86

INVOICED (If desired, observe this plugging.)

Signed Ron Wilson (TECHNICIAN)

DATE 11-12-86 WK

INV. NO. 15326