

2 030432

API NUMBER 15- 173 -20,085-00-01

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

80'S SWSENE, SEC. 15, T 26 S, R 2 E

2690' feet from S section line

990' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8965

Lease Name Lugriss, Well # 1-BOperator: Stekoll Petroleum Inc.County Sedgwick 107.90Name & Address 1434 K.S.B. Bldg.Well Total Depth 3320' feet125 N. MarketConductor Pipe: Size 5 1/2" feet 3314' / 100 cu. ft.Wichita, Ks. 67202Surface Casing: Size 8 5/8" feet 205' / 150 cu. ft.Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor United Cementing Co. License Number _____Address Box 712, El Dorado, Ks. 67042Company to plug at: Hour: 08:00 Day: 27 ^{KCC 200} 17 Month: 6 Year: 19 86Plugging proposal received from Ray Stekoll(company name) Stekoll Petroleum Inc. (phone) 316-262-7123

were: Perf. 3182' to 3208' pump 1 cu bulk, 4 cu gel, 50 cu cement
down 5 1/2" csg. to 3100', run 3/4" pipe to 250' + between 5 1/2" +
8 5/8", cement to surface, run tube to 250' + inside 5 1/2" csg.
cement to surface.

Plugging Proposal Received by Alan Thompson
(TECHNICIAN)Plugging Operations attended by Agent?: All X Part _____ None _____Operations Completed: Hour: 17:00 Day: 27 Month: 6 Year: 19 86

ACTUAL PLUGGING REPORT United #1632 pumped 1 cu bulk, 4 cu gel, 50 cu cement.
hole in top of 5 1/2" all materials vis. to surface. Ran 2 1/2" tube to 2950'
spotted 50 cu cement, pulled tube, bit set, ran 3/4" between 5 1/2" + 8 5/8" csg to 273'
pumped 100 cu cement to ann, pulled 3/4", ran 2 1/2" tube inside 5 1/2" to 279'
pumped 50 cu cement vis. to surface, pulled tube, filled csg + annulus with 50 cu
cement.

Remarks: ck. well 6-30-86 cement down app. 50' between csg. 120' inside csg. to full pred. mig.
(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE JUL 11 1986Signed Alan Thompson
(TECHNICIAN) CONSERVATION DIVISION
Wichita, KansasINV. NO. 14337

6-27

FORM CP-2/3
Rev. 01-84