

To:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-173-19042-00-00

SESE NW, Sec. 15, T 26 S, R 2 #E

feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

feet from W/E section line

Operator License # 5088

Lease Name Lygrisse Well # 1

Operator: BO DARAH Oil Co.

County Sedgwick

Name &

Address CANTERBURY LANE

Well Total Depth 2937 feet \$ 95.45

Great Bend, Ks.

Conductor Pipe: Size 4 1/2" feet 3180' / 125 SX

Surface Casing: Size 8 5/8" feet 231' / 135 SX cent.

top Perf. 2914'

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, Ks. 67524 TAG. 545

Company to plug at: Hour: 2:00 PM Day: 9 Month: 5 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO M. Ke Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: sand hole to 2875' dump. 5 SX cent. Pull csq.

Pump. 3 SX hulls, 6 SX gel, 90 SX cent 2% gel, 3 % cc

down 8 5/8" SUR. csq.

Signed Ron Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5:00 PM Day: 9 Month: 5 Year: 1983

ACTUAL PLUGGING REPORT Sanded hole to 2875', dumped 5 SX cent. / bailer

Shot & pulled 2502' 4 1/2" csq., United Cementing # 3741

pumped 3 SX hulls, 6 SX gel, 90 SX cent. 2% gel, 3% cc.

down 8 5/8" surface csq. Pump Press 800#. S.I.P. 300#

Remarks:

I hereby certify that the above plugging instructions were given as herein stated
and that I (did) / did not) observe this plugging.

INVOICED

DATE 5-16-83

INV. NO. 3916-E

RECEIVED
STATE CORPORATION COMMISSION

5/16/83
MAY 16 1983

CONSERVATION DIVISION
Wichita, Kansas

Signed Ron Thompson
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82