

9-17
RECEIVED
KANSAS CORPORATION COMMISSION

2-060089
209
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

OCT 5 1992
10-5-92
CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-173-20,717 ⁰⁰⁻⁶⁰ D-24,306
NE NE NE, SECTION 15 TOWNSHIP 27 RANGE 2E

OPERATOR LICENSE # 100 4950 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR Kansas Corporation Comm.
NAME & 202 W. First, #304
ADDRESS Wichita, KS 67202

LEASE NAME: Hart #2 (H.C.Dev.)
COUNTY: Sedgwick
WELL TOTAL DEPTH: 3527'

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 201'/150 sx

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD X D&A _____

OTHER WELL AS HEREINAFTER INDICATED: 4-1/2" @ 3309' - 65 sx cir to surf

PLUGGING CONTRACTOR: Hogoboom Oilfield Trucking

ADDRESS: _____ LICENSE: _____

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 17 MONTH: 9 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Dave Wertz

COMPANY NAME: KCC PHONE: _____

WERE: _____

PLUGGING PROPOSAL RECEIVED BY: Dave Wertz

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART (_____) NONE (_____)

COMPLETED: HOUR: 3:00 DAY: 17 MONTH: 9 YEAR: 1992

ACTUAL PLUGGING REPORT:

Ran wireline to 3348' - hit bridge - pumped 8 bbl
fresh water into 4-1/2" - tied onto 4-1/2" pull slips
cmt dwn 15/20' on backside of 4-1/2" - filled 8-5/8"
annulus - tied on to 4-1/2" - pumped 100 sx 60/40 4%
gel, 2% cc & 100 lb hulls - well went on vacuum - shut
down - waited 2 hr - ran wireline tag cmt at 2554' -
ran 1" tub to 250' - circ 41 sx cmt to surf.

REMARKS: United #3675

I DID OBSERVE THIS PLUGGING.

/s/ Dave Wertz
Dave Wertz (AGENT)