

2-031036

282
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-173-20,250-00-00

NE, SECTION 7 TOWNSHIP 26 RANGE 2E

OPERATOR LICENSE # 5502 2970 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR Energy Management, Inc.
NAME & 514 Broadmoor Court
ADDRESS Wichita, KS 67206

LEASE NAME: Matson
COUNTY: Sedgwick
WELL TOTAL DEPTH: 3439' 111.76

PIPE: 5-1/2" @ 3438'/125 sx
SURFACE CASING: 8-5/8" @ 204' CTS

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: McPherson Drilling Company
ADDRESS: RR #2, Box 168D, Augusta, KS 67010 LICENSE: 5495

COMPANY TO PLUG AT: HOUR: _____ DAY: 16 MONTH: 7 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Billy McPherson
COMPANY NAME: McPerson Drilling Co. PHONE: 316-775-3078

WERE: Sand to 50' above perfs - dump 6 sx cmt - shoot & pull
csg - set rock bridge 300' to 250' - fill to suf with
cement. Perfs 3316' to 3320'

PLUGGING PROPOSAL RECEIVED BY: District #2 office 8-2-91

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE () AUG 2 1991
COMPLETED: HOUR: _____ DAY: 19 MONTH: 7 YEAR: 1991
CONSERVATION DIVISION
Wichita, Kansas

ACTUAL PLUGGING REPORT:
Pushed plug rock & gravel to 3250' - dumped 6 sx cmt
w/bailer - shot & pulled 1955' of 5-1/2" csg - ran 2-
3/8" tub to 275' - Knebler Concrete #034409 dumped 5
yds slurry mix to surf - pulled tub - filled hole.

REMARKS: _____

I DID OBSERVE THIS PLUGGING.

INVOICED

Don Thompson
Don Thompson (AGENT)

DATE 8-23-91

FORM CP-2/3
REV. 3/90

DW INV. NO. 32759