

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

5-31

API NUMBER: 15-173-20,204-00019-877

SE SE SE, SECTION 7 TOWNSHIP 26 RANGE 2E

OPERATOR LICENSE # 30742 330' FEET FROM S SECTION LINE
OPERATOR PALOMINO PETROLEUM, INC. 330' FEET FROM E SECTION LINE
NAME & 4924 SE 84TH STREET
ADDRESS NEWTON, KS 67114-8827
LEASE NAME: MILLER "C" SWD
COUNTY: SEDGWICK 112.77
WELL TOTAL DEPTH: 3470'
CONDUCTOR PIPE: 5 1/2" @ 3469'
SURFACE CASING: 8 5/8" @ 212'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD X D&A _____ D-19,877

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: D.S. & W. WELL SERVICING
ADDRESS: P.O. BOX 231, CLAFLIN, KS 67525 LICENSE: 6901

COMPANY TO PLUG AT: HOUR: 12:30 DAY: 31 MONTH: 5 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT II

COMPANY NAME: UNITED CEMENTING PHONE: (316) 321-4680
WERE: SAND BACK AND SPOT 6 SACKS OF CEMENT AT 3360'. SHOOT 5 1/2" CASING AT 2047' AND PULL UP TO 280'. CIRCULATE CEMENT FROM 280' TO SURFACE. PULL CASING OUT OF HOLE AND TOP OFF WITH CEMENT.

RECEIVED
KANSAS CORPORATION COMMISSION

PLUGGING PROPOSAL RECEIVED BY: KLEE WATCHOUS

JUL 22 1996
7-22-96

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (X) NONE ()

CONSERVATION DIVISION
WICHITA, KS

COMPLETED: HOUR: 13:30 DAY: 31 MONTH: 5 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED BACK AND SPOTTED 6 SACKS OF CEMENT AT 3360'. SHOT 5 1/2" CASING AT 2047' AND PULLED UP TO 280'. CIRCULATED CEMENT FROM 280' TO SURFACE. PULLED CASING OUT OF HOLE AND TOPPED OFF WITH CEMENT.

REMARKS: 129 SACKS OF CEMENT 60/40 POZ 2% GEL UNITED #3394

I DID ~~NOT~~ OBSERVE THIS PLUGGING.

INVOICED

(AGENT) JERRY CLARK

DATE 7-22-96

INV. NO. 46046