

3-17

2-080037

186
R

RECEIVED
KANSAS CORPORATION COMMISSION
3-31-92
MAR 31 1992
CONSERVATION DIVISION
WICHITA, KS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-173-20,711-00-00

NE SE SW, SECTION 2 TOWNSHIP 27 RANGE 2E

OPERATOR LICENSE # 30752 995 FEET FROM S SECTION LINE
2975 FEET FROM E SECTION LINE

OPERATOR Pipe Recovery, Inc.
NAME & P. O. Box 7
ADDRESS Great Bend, KS 67535

LEASE NAME: Ketteman #1
COUNTY: Sedgwick
WELL TOTAL DEPTH: 3315' 107.73

CONDUCTOR PIPE: 8-5/8" @ 228'

SURFACE CASING: 5-1/2" @ 3313'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Pipe Recovery
ADDRESS: P. O. Box 7, Great Bend, KS 67530 LICENSE: 30752

COMPANY TO PLUG AT: HOUR: 10:30 DAY: 17 MONTH: 3 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Rick Davis
COMPANY NAME: Pipe Recovery PHONE: 793-3922

WERE: Push plug to 2530' - sand back to 2480' (perfs @ 2530' to 2534', 3279' to 3282') - dump 4 sx cmt on sand w/dump bailer - shoot off pipe @ 1800' - pull pipe up to 260' & circ to surface.

PLUGGING PROPOSAL RECEIVED BY: Doug Louis

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 11:00 DAY: 17 MONTH: 3 YEAR: 1992

ACTUAL PLUGGING REPORT:
Pushed plug to 2530' - sanded back to 2480' - dumped 4 sx cmt in sand w/bailer - shot off pipe @ 1850' - pulled pipe to 260' & circulated.

REMARKS: B. J. Services #060450

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 4-24-92
INV. NO. 35025
3-17

Doug Louis
Doug Louis (AGENT)