

2 080091

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 173-20,712-00-00

CE/2E/2<sup>NW</sup> SEC. 1, T 28 S, R 2 XW/E

4620 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152

Lease Name Banks Well # 1

Operator: Lee Banks

County Sedgwick 104.00

Name & Address 200 W. Douglas

Well Total Depth 3200 feet

Wichita, KS

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling License Number 5302

Address Wichita, KS 67202

Company to plug at: Hour: 11:30 Day: 17 Month: 6 Year: 19 85

Plugging proposal received from Randy Knotts

(company name) Red Tiger (phone)

were: Condition hole-Circulate 35 sacks of cement at 1100 feet through drill pipe; 35 sacks of cement at 260 feet; 25 sacks at 60 feet; and 10 sacks in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
7-3-85  
JUL 03 1985

Plugging Proposal Received by Ralph E. O'Connor  
CONSERVATION DIVISION (TECHNICIAN)  
Wichita, Kansas

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 07:30 Day: 19 Month: 6 Year: 19 85

ACTUAL PLUGGING REPORT Ran drill pipe to 1100 feet and circulated 35 sacks of cement. Pulled drill pipe to 260 feet and spotted 35 sacks of cement. Pulled drill pipe to 60 feet and spotted 25 sacks of cement. Ran one joint of drill pipe in the rat hole and circulated 10 sacks of cement to surface.

Remarks: United Ticket #10764---reported by Mike Rempe  
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did/did not) observe this plugging.

DATE 7-11-85

Signed Ralph E. O'Connor (TECHNICIAN)

INV. NO. 8839