

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 3581
Name: Red Oak Energy, Inc.
Address: 7701 E. Kellogg ste. 710
City/State/Zip: Wichita, KS. 67207
Purchaser: Plains
Operator Contact Person: Kevin Davis
Phone: (316) 652-7373
Contractor: Name: Murfin Drilling Co., Inc
License: 30606
Wellsite Geologist: Scott Banks

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

4-13-06	4-21-06	5-5-06
Spud Date or	Date Reached TD	Completion Date or
Recompletion Date		Recompletion Date

API No. 15 - 199-20324-0000
County: Wallace
_____ ne _____ se Sec. 1 Twp. 15 S. R. 41 East West
2140 feet from (S) / N (circle one) Line of Section
660 feet from (E) / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE (SE) NW SW
Lease Name: Joe Smith Well #: 1-1
Field Name: Ladder Creek extension
Producing Formation: Morrow
Elevation: Ground: 3706 Kelly Bushing: 3717
Total Depth: 5130 Plug Back Total Depth: 5089
Amount of Surface Pipe Set and Cemented at 391 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set 2739 Feet
If Alternate II completion, cement circulated from 2739
feet depth to surface w/ 500 sx cmt.

Drilling Fluid Management Plan *Alt. #2 KGR 6/21/07*
(Data must be collected from the Reserve Pit)
Chloride content _____ ppm Fluid volume 500 bbls
Dewatering method used Cut Windows, let evaporate, backfill and restore when conditions allowed
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]
Title: President Date: 4-7-07
Subscribed and sworn to before me this 10th day of April
2007.
Notary Public: [Signature]
Date Commission Expires: October 29, 2009

KCC Office Use ONLY

Letter of Confidentiality Received
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

RECEIVED
KANSAS CORPORATION COMMISSION

VICTORIA DAVIS
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 10/29/09

APR 11 2007

CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., INC. 23948

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Ogkley

DATE <u>4-22-06</u>	SEC. <u>1</u>	TWP. <u>153</u>	RANGE <u>41W</u>	CALLED OUT	ON LOCATION <u>1:30 AM</u>	JOB START <u>9:10 AM</u>	JOB FINISH <u>10:00 AM</u>
LEASE <u>J. Smith</u>		WELL# <u>1-1</u>	LOCATION <u>Sharon Springs 832W 15</u>			COUNTY <u>Wallace</u>	STATE <u>Ks</u>
OLD OR NEW (Circle one)			<u>2W 4W</u>				

CONTRACTOR Murfin Drilling Rig 14
 TYPE OF JOB Two Stage Bottom Stage
 HOLE SIZE 7 1/8 T.D. 5130'
 CASING SIZE 5 1/2 DEPTH 5132'
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL DV Tool DEPTH 2735'
 PRES. MAX 1300# MINIMUM
 MEAS. LINE SHOE JOINT 42.61'
 CEMENT LEFT IN CSG. 42.61'
 PERFS.
 DISPLACEMENT 56 Bbls water & 65 Bbls Mud
 EQUIPMENT Total

OWNER Same
 CEMENT
 AMOUNT ORDERED 150 SKS ASC, 2# GEL
5# Gilsomite
500 gals WFR-2

PUMP TRUCK CEMENTER Dean
 # 373-281 HELPER Andrew
 BULK TRUCK
 # 347 DRIVER Jarrod
 BULK TRUCK
 # DRIVER

COMMON	@		
POZMIX	@		
GEL		<u>3 SKS</u>	@ <u>15.00</u> <u>45.00</u>
CHLORIDE	@		
ASC		<u>150 SKS</u>	@ <u>12.80</u> <u>1920.00</u>
	@		
<u>Gilsomite</u>		<u>7.50 #</u>	@ <u>.65</u> <u>487.50</u>
	@		
<u>WFR-2</u>		<u>500 gals</u>	@ <u>1.00</u> <u>500.00</u>
	@		
	@		
	@		
HANDLING		<u>176 SKS</u>	@ <u>1.70</u> <u>299.20</u>
MILEAGE		<u>74 SK/mile</u>	<u>800.80</u>
			TOTAL <u>4052.50</u>

REMARKS:

Mix 500gals WFR-2 & 150 SKS ASC,
2# GEL, 5# Gilsomite, Wash Pump
& Line, Disp 56 Bbls water & 65 Bbls
Mud, Had lift Pressure 80 psi,
Plug landed at 1300#. Float Held,
Drop Dart open DV Tool w/ 800#.

Thank you

CHARGE TO: Red Oak Energy
 STREET _____
 CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB	<u>5132'</u>	
PUMP TRUCK CHARGE		<u>1660.00</u>
EXTRA FOOTAGE	@	
MILEAGE	<u>65 miles</u>	@ <u>5.00</u> <u>325.00</u>
MANIFOLD	@	
<u>Head Rental</u>	@	<u>100.00</u>
	@	
TOTAL <u>2085.00</u>		

PLUG & FLOAT EQUIPMENT

<u>5 1/2</u>	<u>APU Float shoe</u>		<u>263.00</u>
	<u>flex Latch down plug</u>	@	<u>350.00</u>
<u>2</u>	<u>- Baskets</u>	@ <u>140.00</u>	<u>280.00</u>
<u>10</u>	<u>- Centralizers</u>	@ <u>50.00</u>	<u>500.00</u>
<u>1</u>	<u>- DV TOOL</u>	@	<u>3300.00</u>
<u>10</u>	<u>- Reciprocating</u>	@ <u>35.00</u>	<u>350.00</u>
	<u>scratchers</u>		
TOTAL			<u>5043.00</u>

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____

ALLIED CEMENTING CO., INC. 23949

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley

DATE <u>4-22-06</u>	SEC. <u>1</u>	TWP. <u>15s</u>	RANGE <u>41W</u>	CALLED OUT	ON LOCATION <u>1:30 PM</u>	JOB START <u>1:00 PM</u>	JOB FINISH <u>2:00 PM</u>
LEASE <u>J. Smith</u>	WELL# <u>1-1</u>	LOCATION <u>Sharon Springs 8s 2w 1s</u>			COUNTY <u>Wallace</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)							

CONTRACTOR <u>Murfin Drlg Rig 14</u>	OWNER <u>Sqme</u>
TYPE OF JOB <u>Two Stage Bottom Top Stage</u>	
HOLE SIZE <u>7 7/8</u>	T.D.
CASING SIZE <u>5 1/2</u>	DEPTH <u>2735'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT <u>65 Bbls</u>	

EQUIPMENT

PUMP TRUCK	CEMENTER <u>Dean</u>
# <u>373-281</u>	HELPER <u>Andrew</u>
BULK TRUCK	
# <u>347</u>	DRIVER <u>Jarrod</u>
BULK TRUCK	
# <u>394</u>	DRIVER <u>Mike</u>

CEMENT

AMOUNT ORDERED 500 SKS Lite Yu # Flo Seal

COMMON	@		
POZMIX	@		
GEL	@		
CHLORIDE	@		
ASC	@		
<u>Liteweight 500sks</u>	@	<u>9.70</u>	<u>4830.00</u>
<u>Flo Seal 125#</u>	@	<u>1.80</u>	<u>225.00</u>
	@		
	@		
	@		
	@		
HANDLING <u>539 SKS</u>	@	<u>1.70</u>	<u>916.30</u>
MILEAGE <u>79/gal/mile</u>			<u>2452.85</u>
TOTAL			<u>8449.75</u>

REMARKS:

Plug Rat Hole w/ 15 sks
Plug mouse hole w/ 10 sks
Mix 500 SKS Lite Yu # Flo Seal down
5/2 csg. wash pump & line.
Cement did circulate.
Had good lift pressure. Plug
landed and took 1600# to close
DV Tool

Thank you

CHARGE TO: Red Oak Energy

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB		
PUMP TRUCK CHARGE		<u>860.00</u>
EXTRA FOOTAGE	@	
MILEAGE <u>65 miles</u>	@	<u>N/C</u>
MANIFOLD	@	
	@	
	@	

TOTAL 860.00

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	
TOTAL _____		

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE *Dean*

PRINTED NAME

ALLIED CEMENTING CO., INC.

25910

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Oakley

DATE <u>4-13-06</u>	SEC <u>1</u>	TWP. <u>15^s</u>	RANGE <u>41^w</u>	CALLED OUT	ON LOCATION <u>7:45 PM</u>	JOB START <u>9:45 AM</u>	JOB FINISH <u>10:15 PM</u>
LEASE <u>J. Smith</u>	WELL # <u>1-1</u>	LOCATION <u>Sharon Springs 85-24</u>		COUNTY <u>Wallace Kan</u>	STATE		
OLD OR NEW (Circle one)		<u>15-24-14N</u>					

CONTRACTOR MurFin Dals Co #14

TYPE OF JOB Sur Face

HOLE SIZE 12 1/4 T.D. 394

CASING SIZE 8 5/8 DEPTH 394

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 42.08'

CEMENT LEFT IN CSG. 42.08'

PERFS.

DISPLACEMENT 22 1/2 BBL

OWNER Same

CEMENT AMOUNT ORDERED 315 SKS com

3%cc - 2%lel

COMMON	<u>315 SKS</u>	@	<u>11⁰⁰</u>	<u>3,465⁰⁰</u>
POZMIX		@		
GEL	<u>6 SKS</u>	@	<u>15⁰⁰</u>	<u>90⁰⁰</u>
CHLORIDE	<u>11 SKS</u>	@	<u>42⁰⁰</u>	<u>462⁰⁰</u>
ASC		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>332 SKS</u>	@	<u>1⁷⁰</u>	<u>564⁴⁰</u>
MILEAGE	<u>7¢ per SK/cent</u>			<u>1,510⁶⁰</u>
TOTAL				<u>6,092⁰⁰</u>

EQUIPMENT

PUMP TRUCK CEMENTER Terry

102 HELPER Walf

BULK TRUCK

394 DRIVER milke

BULK TRUCK

DRIVER

REMARKS:

Cement did not

SERVICE

DEPTH OF JOB				
PUMP TRUCK CHARGE				<u>735⁰⁰</u>
EXTRA FOOTAGE	<u>94'</u>	@	<u>160¢</u>	<u>56⁴⁰</u>
MILEAGE	<u>65- miles</u>	@	<u>5⁰⁰</u>	<u>325⁰⁰</u>
MANIFOLD		@		
		@		
		@		

CHARGE TO: Red Oak Energy

STREET _____

CITY _____ STATE _____ ZIP _____

TOTAL 1,116⁴⁰

PLUG & FLOAT EQUIPMENT

	<u>8 5/8</u>			
1- Centralizer		@		<u>55⁰⁰</u>
1- Baffle Plate		@		<u>45⁰⁰</u>
1- Surface Plug		@		<u>55⁰⁰</u>
		@		
		@		
TOTAL				<u>155⁰⁰</u>

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Greg Church

Greg Church
PRINTED NAME