

State of Kansas



15-163-30158-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
JUN 14 1966
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
6/14/66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Wenrich of D & D Drilling Co. has this
date requested permission to plug the following described well:

Mr. Wenrich guarantees payment of the plugging fee.

Operator's full Name: Max Cohen

Complete Address: Box 13528 Phoenix, Arizona

Lease Name: Griffith Well No. 1

Location: E/2 SW NW Sec. 13 Twp. 9 Rge. 16 (E)(W)X

County Rooks Total Depth 3500 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wenrich was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540 Ft.
and displace 25 sax cement thru drill pipe. Heavy mud to 150 Ft.
set cementing plug and displace 20 sax cement thru drill pipe.
Heavy mud to 40 Ft. set cementing plug, 1/3 sax hulls and 10 sax
cement to base of cellar. Plug rat hole with 2 sax cement.

Very truly yours,

Lia Massey
Conservation Division Agent