

State of Kansas



15-163-01011-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

3/29/66 RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1966
COMMUNICATIONS SECTION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. CRAWFORD of Geo. Crawford Oil Co. has this
date requested permission to plug the following described well:

Mr. CRAWFORD guarantees payment of the plugging fee.

Operator's full Name: Geo. Crawford Oil Co.

Complete Address: Box 93 Natoma Kansas

Lease Name: William KCC TAP HARBO Well No. 1

Location: SW-NE-NE Sec. 1 Twp. 9 Rge. 17 (E)(W) X

County Rooks Total Depth 1240 Oil Well

Gas Well Input Well SWD Well D & A ⊗ Lost Hole X

Mr. CRAWFORD was instructed to plug the well as follows:

Set Pits. Circ. hole w/ Heavy mud. set cementing Plug At 540'
and displace 12 sack cem. thru drill pipe. Heavy mud to 200' - set
Cementing Plug & displace 20 sack cem. thru drill pipe - Heavy
mud to 40' - set cementing plug 1/2 sack Halls and 10 sack
cement to base of cellar.

Very truly yours,

Geo. Massey
Conservation Division Agent