

State of Kansas



15-163-20037-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1967

CONSERVATION DIVISION
Wichita, Kansas

7/24/67

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Burton of Pickrell Drilling Company has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 4 th Nat'l Bank Building Wichita, Kansas

Lease Name: Hrabe "B" Well No. 2
Wichita-Kansas

Location: C N 1/2 S 1/2 NW
SW SE NE Sec. 3 Twp. 9 Rge. 17 (E)(W) X

County _____ Rooks _____ Total Depth _____ Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Burton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace

90 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with

2 sc cement.

Very truly yours,

Leo J. Messing
Conservation Division Agent