



15-163-20135-0000

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Miller of L. J. Dreiling has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Co.

Complete Address: Victoria, Ks.

Lease Name: Hrabe Well No. 1

Location: NE SE NW NE Sec. 3 Twp. 9 Rge. 17 (E)(W) XX

County: Rooks Total Depth 3467' Oil Well         

Gas Well          Input Well          SWD Well          D & A XX Lost Hole         

Mr. Miller was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace 70 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc cement.

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 14 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

Very truly yours,

Leo J. Messer  
 Conservation Division Agent

10/14/68