

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 8 1970
CONSERVATION DIVISION
Wichita, Kansas
4-8-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Martin Explorations & Abercrombie Drilling, Inc.

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Kobler Well No. 1

Location CNW-NW-NE Sec. 27 Twp. 8 Rge. (E) (W) 2

County Graham Total Depth 3910'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Abercrombie Drilling, Incorporated.

Address 801 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 11:30 AM Day 6 Month 4 Year 1970

The above well was plugged as follows:

201'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 100 Sx. cement
thru DP from 1125' to 800'. Pulled DP to 215' and displaced 25 Sx. cement thru DP
from 215' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 4/8/70
INV. NO. 1694-u