

15-065-02707-00-01

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION
DEC 20 1971
CONSERVATION DIVISION
Wichita, Kansas

12-20-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company,

Complete Address Box #553, Russell, Kansas.

Lease Name Holly North LKC Unit Well No. 101

Location SW ^{SW} - NW Sec. 28 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3888'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 12:00 M Day 15 Month 12 Year 1971

The above well was plugged as follows:

225'--8 5/8" Surface casing, cement circulated with 175 Sx.

3888'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 3877'. Top perforations @ 3733'.

Pushed plug to 3500', sanded well back to 3475' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing (650') and squeezed well initially with 5 sacks hulls and 12 sacks gel and followed with 110 Cu. Ft. cement from 1150' to 825' then 14 sacks gel from 825' to 250' and followed with 30 Cu. Ft. cement from 250' to 175' then 4 sacks gel from 175' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-350#. Final shut-in pressure-300#. (By Halliburton.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols

Well Plugging Supervisor

DATE 1-6-72INV. NO. 4840-U