

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
2-14-1974
FEB 14 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company,

Complete Address 710 Sutton Place, Wichita, Kansas.

Lease Name Holly LKC Unit North Well No. 201

Location SW-NW-SW Sec. 28 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3886'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 8:30 PM Day 11 Month 2 Year 1974

The above well was plugged as follows:

232'--8 5/8" Surface casing, cement circulated with 175 Sx.
3886'--5 1/2" Production casing cemented on bottom with 125 Sx. No plug-back indicated,
Top perforations from 3732' to 3736'. 5 1/2" has been squeezed @ 1720' with 150 Sx.
cement.

Sanded well back to 3720' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(661') and squeezed well initially with 5 sacks hulls and 1 1/2 sacks gel and followed
with 110 Cu. Ft. cement from 1085' to 760' then 13 sacks gel from 760' to 240' and
followed with 30 Cu. Ft. cement from 240' to 165' then 3 sacks gel from 165' to 45'
and finally 10 Cu. Ft. cement from 45' to bottom of cellar. Maximum pump-in pressure
-500#. FSIP-300#. (Mudding & cementing by Halliburton).
I hereby certify that the above well was plugged as herein stated.

Signed: K. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 2/18/74
INV. NO. 8572-W