

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 43-42

LOCATION NW SE SW

SEC. 29TWP. 8 RGE. 24^W

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease B. A. Fox

Operator The Texas Co Address Wichita, Kans

Field _____ County Graham

Total Depth 4403 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 317' circulated with cement - 7" at 3951' with
150 sax cement behind - Lane Wells plugs to 3645' - top
perforations at 3490'.

Set plug at 3450' sand and 5 sax cement run with dump bailer,
pulled 3181' 7" casing, filled with mud to 310', set rock and
20 sax cement, mud to 30', set rock and 10 sax cement to
bottom cellar.

J. P. [Signature]
District Conservation Agent

Date 9-20-52

RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1952
9-25-1952
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC-22T-1 R249
BOOK PAGE 43 LINE 42