

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

FEB 9 1962
2-21-1962
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham

Location: NE NE SE Sec. 29 Twp. 8 Rge. _____ (E) _____ (W) 24

Name of Field: _____ Total Depth: 3947

I have this date completed supervision of plugging of:

Lease Name: Keith Well No. 1

Operator's Full Name: Morganstern Oil Operations

Complete Address: Box 2526 Wichita (8), Kansas

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 3PM Day 15 Month 2 Year 62

The above well was plugged as follows:

8 5/8" 274' circulated with cement - 5 1/2" 3944' with 150 sax cement PB and perforated 3758' .

Filled with sand to 3740', set 4 sax cement with dump bailer, pulled 1567' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" (29 sax Gel). displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Knight Co. pump truck .

Signed: Leon Peety
Conservation Division Agent

Reviewed: Harold Wheeler
Field Supervisor

Remarks:

INVOICED
DATE 3/6/62
INV. NO. 4588-w