

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 100-45

LOCATION NW NE SE

SEC. 29 TWP. 8 RGE. 24 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 3 Lease Keith

Operator El Dorado Refg Co Address Box 209 Russell, Kans

Field _____ County Graham

Total Depth 3916 Feet.

Plugging Contractor C. E. Shull

Plugging Contractor's License No. 8

Address _____
(Describe Briefly the manner in which the well was plugged)

8 5/8" at 315', circulated with cement - 5 1/2" at 3916' with
150 sax cement behind - Lane Wells plugs to 3796' - perforated
3753'

Filled with sand to 3740', set 4 sax cement with dump bailer,
pulled 3400' 5 1/2" - filled hole with mud to 310', set rock bridge
and 20 sax cement, mud to 35', set rock and 10 sax cement to
bottom cellar.

E. J. Kelly
District Conservation Agent

Date 10-6-56

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 X 1956
10-9-1956
CONSERVATION DIVISION

PLUGGING
FILE SEC 29 T. 8 R. 24 W
BOOK PAGE 100 LINE 45