

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1971
CONSERVATION DIVISION
Wichita, Kansas
12-20-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company,

Complete Address Box #553, Russell, Kansas.

Lease Name Holly North LKC Unit Well No. 304-S

Location SW-NE-NE Sec. 29 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3900'

Abandoned Oil Well Gas Well Water Supply Well KCC ZAP Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 2:00 PM Day 15 Month 12 Year 1971

The above well was plugged as follows:

225 ^{KCC ZAP} 218' -- 8 5/8" Surface casing, cement circulated with 175 Sx.

3898' -- 5 1/2" Production casing cemented on bottom with 125 Sx. No plug back nor perforations indicated.

Pushed plug to 3500', sanded well back to 3475' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing (92') and squeezed well with 110 Cu. Ft. cement from 1110' to 785'

then 13 sacks gel from 785' to 250' and followed with 30 Cu. Ft. cement from 250' to 175'

then 4 sacks gel from 175' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-800#. Final shut-in pressure--100#.

(Mudding and cementing operations performed by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. S. Dickel
Well Plugging Supervisor

DATE 1-6-72
INV. NO. 4841-W